



**Rig #77
Inventory**

Drawworks:

- 2007 Taylor RT 5000 drawworks rated at 500 HP
- (1) Caterpillar C-15 engines, EPA Tier 3 certified

Mast:

- Taylor RT 5000 square set derrick, 70' high
- 200,000 lbs static hook load

Substructure:

- Height 13.6' with 15' K.B. elevation

Mud Pumps:

- (2) Gardener Denver PZ-7 Triplex pumps
- (2) Detroit 60 series, 600 HP engines, EPA Tier 3 certified
- (2) 5' x 6' x 11' centrifugal charge pumps rated 3000 PSI

Mud System:

- (1) 240 bbl, 3 compartment mud tank,
- (1) 5'x 6'x 11' 50 HP mix centrifugal
- (1) 5'x 6'x 11' 50HP desilter pump with 12 cones
- (2) Fluid system single deck, 4 panel shakers
- (1) Mud cleaner with (8) desilter cones
- (1) 220 bbl mud tank (by request)

Rotary Table:

- DSM 18" rotary table
- 200,000 lbs rotary load

Generator:

- (1) Magnum 235 KW, EPA Tier 3 Certified

Drilling, Tripping Blocks & Swivel:

- (2) McKisick 6 line, 100 ton blocks
- PG 60 Western Rubber, 100 ton swivel



BARBOUR WELL, INC.

GEOTHERMAL, OIL & GAS DRILLING

